



LAYOUT POWER STATION E TRANSFORMER STATION - SCALA 1:1000



Ubicazione inverter



Ubicazione trasformatori


DATI TECNICI E PARTICOLARI POWER STATION



SUN2000-315KTL-H10  
Technical Specifications

| Efficiency                               |  |
|--|--|
| Max. Efficiency                          | 99.00%   |
| European Efficiency                      | 98.60%   |
| Input                                    |  |
| Max. Input Voltage                       | 1,500 V  |
| Max. Current per MPPT                    | 30 A   |
| Max. Short-Circuit Current per MPPT      | 30 A   |
| Start Voltage                            | 550 V  |
| MPPT Operating Voltage Range             | 90 V ~ 1,080 V                                 |
| Nominal Input Voltage                    | 1,080 V  |
| Number of Inputs                         | 10   |
| Number of MPPT Trackers                  | 5  |
| Output                                   |  |
| Nominal AC Active Power                  | 203,000 W                                      |
| Max. AC Apparent Power                   | 215,000 VA                                     |
| Max. AC Active Power (SMP+T)             | 215,000 W                                      |
| Nominal Output Voltage                   | 800 V, 5W ~ 4%<br>50 Hz / 60 Hz                |
| Rated AC Grid Frequency                  | 50 Hz / 60 Hz                                  |
| Nominal Output Current                   | 146.4 A  |
| Max. Output Current                      | 155.2 A  |
| Adjustable Power Factor Range            | 0.8 LG ~ 0.8 LD                                |
| Max. Total Harmonic Distortion           | < 3%   |
| Protection                               |  |
| Island-side Disconnection Device         | Yes  |
| Anti-islanding Protection                | Yes  |
| AC Overcurrent Protection                | Yes  |
| DC Reverse-polarity Protection           | Yes  |
| PV-array String Fault Monitoring         | Yes  |
| DC Surge Arrester                        | Type II  |
| AC Surge Arrester                        | Type II  |
| DC Insulation Resistance Detection       | Yes  |
| Residual Current Monitoring Unit         | Yes  |
| Communication                            |  |
| Display                                  | LED Indicators, WLAN + APP                     |
| USB                                      | Yes  |
| RS485                                    | Yes  |
| RS485                                    | Yes  |
| General                                  |  |
| Dimensions (W x H x D)                   | 1,030 x 700 x 385 mm (40.7 x 27.6 x 14.4 inch) |
| Weight (with mounting rack)              | 48 kg (106 lb.)                                |
| Operating Temperature Range              | -25°C ~ 60°C (-13°F ~ 140°F)                   |
| Cooling Method                           | Smart Air Cooling                              |
| Max. Operating Altitude without Derating | 4,000 m (13,122 ft.)                           |
| Relative Humidity                        | 0 ~ 100%                                       |
| DC Connector                             | Standard MC4 5/002                             |
| AC Connector                             | Waterproof Connector + OT/DT Terminal          |
| Protection Degree                        | IP65   |
| Topology                                 | Transformerless                                |

DATI TECNICI E PARTICOLARI TRANSFORMER STATION



STS-3000K-H1  
Technical Specifications

| Input                                    |   |
|--|---|
| Available Inverters                      | SUN2000-300KTL-H0 / SUN2000-315KTL-H0   |
| AC Power                                 | 3,250 KVA (840°C) / 2,960 KVA (850°C)   |
| Max. Inverters Quantity                  | 16  |
| Rated Input Voltage                      | 800 V   |
| Max. Input Current at Nominal Voltage    | 2,482.7 A   |
| LV Main Switches                         | ACS (2000 A / 800 V / 3P, 1 pole), MCCB (250 A / 800 V / 3P, 16 pole)   |
| Output                                   |   |
| Rated Output Voltage                     | 10 kV, 11 kV, 15 kV, 20 kV, 22 kV, 23 kV, 30 kV, 33 kV, 35 kV, 38 kV, 39 kV, 40 kV, 42 kV, 44 kV, 46 kV, 48 kV, 50 kV, 52 kV, 54 kV, 56 kV, 58 kV, 60 kV, 62 kV, 64 kV, 66 kV, 68 kV, 70 kV, 72 kV, 74 kV, 76 kV, 78 kV, 80 kV, 82 kV, 84 kV, 86 kV, 88 kV, 90 kV, 92 kV, 94 kV, 96 kV, 98 kV, 100 kV |
| Frequency                                | 50 Hz   |
| Transformer Type                         | Oil-immersed, Conservator Type  |
| Transformer Tappings                     | ± 2 x 2.5%  |
| Transformer Oil Type                     | Mineral Oil (PCB Free)  |
| Transformer Vector Group                 | Dyn11   |
| Transformer Min. Peak Efficiency Index   | In accordance with IEC 60076-1  |
| Transformer Load Losses                  | 30.1 kW   |
| Transformer No-load Losses               | 2.51 kW   |
| Impedance (HV-LV, LV2)                   | 7% (D ~ 110%) @ 3,250 KVA   |
| MP Switchgear Type                       | SPS Gas Insulated, 17.5 kV  |
| MP Switchgear Configuration              | 1 Transformer Unit with Circuit Breaker<br>1 Cable Joint with Load Breaker Switch<br>1 Cable Direct Connection Unit   |
| Auxiliary Transformer                    | Dyn11 Type Transformer, 5 kVA, Dyn11  |
| Output Voltage of Auxiliary Transformer  | 400 / 230 Vac   |
| 220 / 127 Vac                            |   |
| Protection                               |   |
| Transformer Monitoring & Protection      | Oil Level, Oil Temperature, Oil Pressure and Buchholz   |
| Protection Degree of MV & LV Room        | IP 54   |
| Internal Arcing Fault MV Switchgear      | IAC-A 20 kA 1s  |
| MV Relay Protection                      | 920U, 50kV/15kV   |
| MV Surge Arrester for MV Circuit Breaker | Equipped  |
| LV Overvoltage Protection                | Type I+II   |
| General                                  |   |
| Dimensions (W x H x D)                   | 6,058 x 2,890 x 4,438 mm (20' HC Container)   |
| Weight                                   | < 15 t (33,069 lb.)   |
| Operating Temperature Range              | -25°C ~ 60°C (-13°F ~ 140°F)  |
| Relative Humidity                        | 0% ~ 95%  |
| Max. Operating Altitude                  | 2,000 m (6,562 ft.)   |
| End-user Color                           | RAL 9003  |
| Communication                            | Modbus RTU, Preconfigured with SmartLogger 3000B  |
| Applicable Standards                     | IEC 62271-202, IEC 60076-1, IEC 60076-2, IEC 62271-200, IEC 61439-1   |
| Features                                 |   |
| Auxiliary Transformer (50 kVA, Dyn11)    | Optional +  |
| 15 kV GIS                                | Optional +  |
| MV Switchgear Upgraded to:               | Optional +  |
| 1 Transformer Unit with Circuit Breaker  | Optional +  |
| 2 Cable Units with Load Breaker Switch   | Optional +  |
| Standard to 20kV to MV Switchgear        | Optional +  |
| IMD                                      | Optional +  |
| STS Interlocking                         | Optional +  |



IMPIANTO FOTOVOLTAICO EG Laguna  
E OPERE CONNESSE  
POTENZA IMPIANTO 13,8 MWp - COMUNE DI PORTOMAGGIORE

Proponente

EG Laguna S.R.L.  
VIA DEI PELLEGRINI 22 - 20122 MILANO (MI) - P.IVA: 11769770964 - PEC: eglaguna@unape.it

Progettazione

Ing. Piero FARENTI, Via Don Giuseppe Corda, SNC -  
03030 Santopadre (FR) - tel.: 0776531040 - e-mail: info@farenti.it  
PEC: piero@pec.farenti.it

Collaboratori

Ing. Andrea FARENTI, Via Don Giuseppe Corda, SNC - 03030 Santopadre (FR)  
tel.: 0776531040 - e-mail: info@farenti.it - PEC: andrea@pec.farenti.it

Coordinamento progettuale

FARENTI S.R.L.  
Via Don Giuseppe Corda, SNC - 03030 Santopadre (FR) - P.Iva 02604750600 -  
Tel. 0776531040 Fax 07761800135

Titolo Elaborato

| Layout power station e transformer station |  | LIVELLO PROGETTAZIONE |  | CODICE ELABORATO | FILENAME | FORMATO | DATA | SCALA |
|--|--|-----------------------|--|------------------|----------|---------|------|-------|
| Progetto definitivo                        |  | VIA-TAV10             |  | -                | A1       | 11/20   | -    | -     |

Revisioni

| REV. | DATA       | DESCRIZIONE | ESEGUITO | VERIFICATO | APPROVATO |
|------|------------|-------------|----------|------------|-----------|
| 00   | 20/07/2021 | -           | AF       | PF         | ENF       |



COMUNE PORTOMAGGIORE  
REGIONE EMILIA ROMAGNA



energy for life